

**NOTES:**

- RAMP LOCATIONS ARE TO BE COORDINATED WITH AND IN CONFORMANCE WITH CROSSWALK WARNING DETAILS SHOWN ON THIS PLAN.
- CLOSED RAMP SHALL HAVE FLARED SIDES WITH A MAXIMUM SLOPE OF 1:1.
- RAMP SHALL HAVE A DRAINAGE SURFACE, TEXTURED TO A DEPTH NOT EXCEEDING 1/8".
- RAMP ARE TO BE CONSTRUCTED AT ALL LOCATIONS SHOWN IN THE PLAN WITHIN A DESIGN 5' FROM CURB OR CONSTRUCTION LINE.
- NO CURB TRANSITION IS NEEDED FOR MAIN CURVES.


**LEGAL DESCRIPTION:**

A PARCEL OF LAND SITUATED IN THE SOUTHEAST ONE-QUARTER OF SECTION 16, TOWNSHIP 16 SOUTH, RANGE 33 EAST, VOLusia COUNTY, FLORIDA, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

FROM A POINT OF REFERENCE BEING THE INTERSECTION OF THE NORTHERLY RIGHT OF WAY LINE OF VILLAGE TRAIL AS PER PLAT OF COUNTRYSIDE P.L.D. UNIT 18-A AS FOUND IN PLAT BOOK 38 ON PAGES 156 AND 157 AGAINST THE PUBLIC RECORDS OF VOLusia COUNTY, FLORIDA (SAD NORTHERLY RIGHT OF WAY OF VILLAGE TRAIL ALSO BEING THE NORTHERLY BOUNDARY OF SAID PLAT OF COUNTRYSIDE P.L.D. UNIT 18-A), AND THE WESTERLY RIGHT OF WAY LINE OF NOVA ROAD (A 100 FOOT WIDE RIGHT OF WAY, ALSO KNOWN AS STATE ROAD 54 AS SHOWN ON SAID PLAT OF COUNTRYSIDE P.L.D. UNIT 18-A); THENCE N. 27°02'20" W. ALONG SAID WESTERLY RIGHT OF WAY LINE OF NOVA ROAD AND DEPARTING NORTHERLY BOUNDARY OF COUNTRYSIDE P.L.D. UNIT 18-A, A DISTANCE OF 1194.99 FEET TO A POINT IN THE NORTHERLY RIGHT OF WAY LINE OF DUNLAWTON BOULEVARD (A 200 FOOT WIDE RIGHT OF WAY), ALSO KNOWN AS STATE ROAD 410, THENCE S. 56°21'11" W. ALONG SAID NORTHERLY RIGHT OF WAY LINE OF DUNLAWTON BOULEVARD A DISTANCE OF 1000.14 FEET, THENCE N. 33°37'22" W. DEPARTING SAID NORTHERLY RIGHT OF WAY LINE OF DUNLAWTON BOULEVARD A DISTANCE OF 438.73 FEET TO THE POINT OF 42.00 FEET, THENCE S. 05°24'29" W. A DISTANCE OF 98.35 FEET, THENCE N. 71°33'54" E. A DISTANCE OF 63.25 FEET, THENCE N. 85°24'29" E. A DISTANCE OF 92.20 FEET, THENCE N. 02°22'52" W. A DISTANCE OF 238.29 FEET, THENCE N. 48°16'45" E. A DISTANCE OF 161.45 FEET, THENCE S. 42°21'52" E. A DISTANCE OF 60.00 FEET, THENCE S. 49°28'45" E. A DISTANCE OF 228.29 FEET, THENCE N. 56°02'38" E. A DISTANCE OF 75.00 FEET, THENCE N. 55°02'38" E. A DISTANCE OF 42.00 FEET, THENCE N. 85°24'29" E. A DISTANCE OF 96.35 FEET, THENCE S. 71°33'54" E. A DISTANCE OF 63.25 FEET, THENCE N. 85°24'29" E. A DISTANCE OF 92.20 FEET TO THE POINT OF BEGINNING OF THIS DESCRIPTION.









**CONSTRUCTION NOTES:**

- THE CONTRACTOR, PRIOR TO CONSTRUCTION, SHALL FIELD LOCATE ALL EXISTING UTILITIES WITHIN OR SURROUNDING THE SITE, FOR POSSIBLE CONFLICT.
- CONTRACTOR SHALL USE STATE RECOMMENDED "BEST MANAGEMENT PRACTICES" TO MINIMIZE SOIL EROSION, SEDIMENTATION, WATER & AIR POLLUTION AND SHALL PROMPTLY RESTORE ANY SUCH DAMAGE. (SEE EROSION CONTROL NOTES)
- CONTRACTOR SHALL RESTORE OFF-SITE AREAS DISTURBED BY CONSTRUCTION TO ORIGINAL CONDITION OR BETTER.
- CONTRACTOR TO MAINTAIN TRAFFIC FLOW DURING CONSTRUCTION.
- CONTRACTOR MAY MAKE MINOR ADJUSTMENTS IN ALIGNMENT & GRADE TO AVOID CONFLICT WITH EXISTING UTILITIES, STRUCTURES, TREES OR TO BETTER MATCH EXISTING FIELD CONDITIONS.
- CONTRACTOR SHALL RECORD AND SUBMIT TO PROJECT ENGINEER ACCURATE AS BUILT INFORMATION.



**CONSTRUCTION NOTES:**

- REQUIRED COMPACT FOR NON-BUILDABLE SITES IS 95%.
- ALL PROPOSED UTILITIES ARE TO BE INSTALLED UNDERGROUND.




**EROSION AND SEDIMENT CONTROL NOTES:**

- Sediment basins and traps, perimeter ditches, sediment barriers and other measures intended to trap sediment shall be constructed as a first step in any land-disturbing activity and shall be made functional before any topsoil disturbance takes place.
- All sediment control measures are to be adjusted to meet field conditions at the time of construction and be maintained prior to any grading or disturbance of existing surface material on balance of site. Permanent sediment barriers shall be constructed to prevent sediment or trash from leaving the project site.
- Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the site. Temporary soil stabilization shall be applied within seven days to denuded areas that may not be at final grade but will remain undisturbed for longer than 30 days. Permanent stabilization shall be applied to areas that are to be left undisturbed for more than one year.
- A permanent vegetative cover shall be established on denuded areas not otherwise permanently stabilized. Permanent vegetation shall not be considered established until a ground cover is achieved that, in the opinion of the Reviewer, is uniform, mature enough to survive and will inhibit erosion.
- Surface runoff from disturbed areas that is comprised of flow from drainage areas greater than or equal to three acres shall be controlled by a sediment basin. The sediment basin shall be designed and constructed to accommodate the anticipated sediment loading from the land-disturbing activity. The outlet device or system design shall take into account the total drainage area flowing through the disturbed area to be served by the basin.
- After any significant rainfall, sediment control structures will be inspected for integrity. Any damaged structures shall be corrected immediately.
- Concentrated runoff shall not flow down cut or fill slopes unless contained within an adequate temporary or permanent channel, flume or slope drain structure.
- Whenever water seeps from a slope face, adequate drainage or other protection shall be provided.
- Sediment will be prevented from entering any storm drain system, ditch, or channel. All storm water shall be treated or treated during construction shall be treated so that sediment-laden water cannot enter the conveyance system without first being filtered or otherwise treated to remove sediment.
- Before temporary or newly constructed stormwater conveyance channels are made operational, adequate outlet protection and any required temporary or permanent channel lining shall be installed in both the conveyance channel and outlet.
- When work in a low watercourse is performed, precautions shall be taken to minimize encroachment, control sediment transport and stabilize the work area to the greatest extent possible during construction. Nonerodible material shall be used for the construction of conveyance and outfalls. Erosion fill may be used for the structure if approved by the Reviewer. Sediment control structures shall be inspected and maintained as needed. The Developer, owner, and/or contractor shall be continuously responsible for all sediment leaving the property. Sediment control measures shall be in working condition at the end of each working day.
- Where construction vehicles access routes intersect paved public roads, provisions shall be made to minimize the transport of sediment by tracking onto the paved surface. When sediment is transported onto a paved road surface with curbs and gutters, the road shall be cleaned thoroughly at the end of each day. Sediment shall be removed from the roads by shoveling or sweeping and transported to a sediment control disposal area. Street sweeping shall be allowed only after sediment is removed in this manner.
- This provision shall apply to individual subdivision lots as well as to larger land-disturbing activities.
- All temporary erosion and sediment control measures shall be removed within 30 days after final site stabilization or after the temporary measures are no longer needed, in the opinion of the Reviewer. Disturbed soil areas resulting from the disposition of temporary measures shall be permanently stabilized to prevent further erosion and sedimentation.
- Properties and waterways downstream from construction sites shall be protected from sediment deposition and erosion.
- Final site preparation shall be completed in conjunction with construction of each phase.
- Erosion control design and construction shall follow the requirements in Index Nos. 101, 102, and 103 of FDOT Roadway and Traffic Design Standards.

**PROJECT DATA:**

Project Area	67,465 Sq.Ft.	1.548 Acres
PROPOSED:		
Building Coverage	6,825 Sq.Ft.	10.1%
Stairways	1,337 Sq.Ft.	2.0%
Parking Lot	15,062 Sq.Ft.	22.3%
Green Areas & Pond	44,241 Sq.Ft.	65.6%
Density:	6,825 Sq.Ft. / 67,465 Sq.Ft. = 10.1%	
Project Zoning:	Planned Commercial Development (PCD)	
Proposed Land Use:	General Office Building	
Parking Required:	6,825 Sq.Ft. / 200 = 35 Spaces	
Bicycle Parking:	35 Spaces x 0.05 = 2 Spaces	
Parking Provided:	35 Spaces including 4 Handicapped	
Water Provider:	City of Port Orange Utilities	
Sewer Provider:	City of Port Orange Utilities	
Soils - S.C.S. #4, Astutula Fine Sand, 0-8% Slopes		
100 Year Flood Plain Not Applicable to Project		
Owner or their successors will be responsible for maintenance of all on site infrastructure as approved for construction.		
Owner: Mr. Chris Elliot 650 Fernhill Drive Port Orange, FL 32127 (904) 788-4275		
Engineer: Allen A. Davis, P.E. 103 W. Wisconsin Ave. #104 Deland, FL 32720 (904) 728-7475		
Developer: F.J. Graham Construction P.O. Box 291543 Port Orange, FL 32129 (904) 756-1095		
Boundary and topo information taken from survey by Service Erosion Land Surveyors, 3859 S. Nova Rd., Port Orange, FL 32127.		
SJRWMD Permit #4-127-0024		
Tax Parcel #6308-00-07-0015		



**PROJECT DATA:**

Project Area	67,465 Sq.Ft.	1.548 Acres
PROPOSED:		
Building Coverage	6,825 Sq.Ft.	10.1%
Stairways	1,337 Sq.Ft.	2.0%
Parking Lot	15,062 Sq.Ft.	22.3%
Green Areas & Pond	44,241 Sq.Ft.	65.6%
Density:	6,825 Sq.Ft. / 67,465 Sq.Ft. = 10.1%	
Project Zoning:	Planned Commercial Development (PCD)	
Proposed Land Use:	General Office Building	
Parking Required:	6,825 Sq.Ft. / 200 = 35 Spaces	
Bicycle Parking:	35 Spaces x 0.05 = 2 Spaces	
Parking Provided:	35 Spaces including 4 Handicapped	
Water Provider:	City of Port Orange Utilities	
Sewer Provider:	City of Port Orange Utilities	
Soils - S.C.S. #4, Astutula Fine Sand, 0-8% Slopes		
100 Year Flood Plain Not Applicable to Project		
Owner or their successors will be responsible for maintenance of all on site infrastructure as approved for construction.		
Owner: Mr. Chris Elliot 650 Fernhill Drive Port Orange, FL 32127 (904) 788-4275		
Engineer: Allen A. Davis, P.E. 103 W. Wisconsin Ave. #104 Deland, FL 32720 (904) 728-7475		
Developer: F.J. Graham Construction P.O. Box 291543 Port Orange, FL 32129 (904) 756-1095		
Boundary and topo information taken from survey by Service Erosion Land Surveyors, 3859 S. Nova Rd., Port Orange, FL 32127.		
SJRWMD Permit #4-127-0024		
Tax Parcel #6308-00-07-0015		

**A.A.D. CIVIL ENGINEERING INC.**

**PROJECT: SITE DEVELOPMENT PLAN FOR ELLIOT OFFICE BUILDING**

**REVISIONS:**

DATE	REVISION
8/1/08	PER ORDERS REQUEST
8/1/08	USED 6" CURBS - RECORDED BUILDING
11/1/08	PER CITY ENGINE COMMENTS OF 11/1/08

**JOB # DDB-038**

**SCALE 1" = 30'**

**DATE 8/26/08**

**DRAWN MTC**

**SHEET ONE OF ONE**

**103 W. WISCONSIN AVENUE - SUITE 108 - DELAND, FLORIDA 32720**

**PHONE (904) 740-1484 FAX 788-7475 EMAIL MEASH@TODTOD.COM**